

7

BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Name of Work: Providing and Asphalting to Pot hole filling and road cutting in Dasarahalli ward No:15

			Est. Cost Rs				10.00	Lakhs	
Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.141/I.19.1 PW, P & IWTD -SR 2015-16)								
	Kempe Gowda Nagara	Cum	14	4.40	2.50	0.30	46.20		
	Bhuvaneshwari Nagar		10	4.00	2.00	0.30	24.00		
	Officer model Colony		7	3.00	2.50	0.30	15.75		
	Grape Garden		9	5.00	1.00	0.30	13.50		
	Nrupatunga Nagara		9	4.50	2.00	0.30	24.30		
	Kalahasti Nagara		13	4.50	1.50	0.30	26.32		
	Kasturi Nagara		11	5.50	2.00	0.30	36.30		
	SM Road		9	5.00	1.00	0.30	13.50		
	Pampa Mahakavi Road		8	4.00	4.00	0.30	38.40		
	Ramesh Road		10	5.50	2.50	0.30	41.25		
	Maheshwari Temple Road		9	4.75	4.50	0.30	57.71		
	Masidi Road		5	5.50	2.50	0.30	20.62		
	Basic Rate	77.00					357.85	83.16	29759.00
	Add Area Weightage 8%	6.16							
	Total	83.16							
2	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2015-16, P.No.154, I No.20.18)								
		Cum	14	4.40	2.50	0.25	38.50		
			10	4.00	2.00	0.25	20.00		
			7	3.00	2.50	0.25	13.12		
			9	7.00	1.00	0.25	15.75		
			9	6.00	2.00	0.25	27.00		
			13	5.50	1.50	0.25	26.81		
			11	4.00	3.00	0.25	33.00		
			9	7.00	1.00	0.25	15.75		
			8	5.00	4.00	0.25	40.00		
			10	4.00	3.50	0.25	35.00		
			9	4.00	2.00	0.25	18.00		
			5	8.00	1.00	0.25	10.00		
							292.93	1713.96	502070.00
	Basic Rate	1587.00							
	Add Area Weightage 8%	126.96							
	Total	1713.96							

S	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
3	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications - Filling pot holes and patch repairs with bituminous concrete, 40mm .(PWD SR 2015-16, P.No. 265, I No. 35.5)								
			14	4.40	2.50		154.00		
			10	4.00	2.00		80.00		
			7	3.00	2.50		52.50		
			9	7.00	1.00		63.00		
			9	6.00	2.00		108.00		
			13	5.50	1.50		107.25		
			11	4.00	3.00		132.00		
			9	7.00	1.00		63.00		
			8	5.00	4.00		160.00		
			10	4.00	3.50		140.00		
			9	4.00	2.00		72.00		
			5	8.00	1.00		40.00		
	Basic Rate	343.00					1171.75	370.44	434063.00
	Add Area Weightage 8%	27.44							
	Total	370.44							
4	Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 4 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete (PWD SR 2015-16, P. 141 and 147 / Item No. 17.1 and 17.4)								
		Cheque	Qty Vide Item No 01				357.85	78.24	27998.00
5	Miscellaneous and other unforeseen charges								6110.00
								Total	1000000.00

(Rupees Ten Lakhs Only)

Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.